



Construction & Estimating Firm

(305) 433-6444 info@iambuilders.com

Home 2 Suites

Pricing Based on Zip Code: 91367

INSTRUCTIONS:
 -Blue boxes require your price to be inputted or reviewed.
 -Gray boxes leave empty
 -For each item being subcontracted, add 30-40% in the column labeled "Est. Sub. Markup". This will cover Supervision and Profit for your subcontractor.

Terms and Conditions/Disclaimer: The quantities, numbers, scope, or any other information contained in this document has been compiled to the best of our knowledge. By utilizing or deriving any of the information contained in this document, you accept the information and quantities as accurate and waive any rights to any claims for errors in information. I AM Builders L.L.C. does not warranty any of the information contained in this document. The information contained in this document are for informational purposes only and to be used as a guideline for quantities and pricing. It is the responsibility of the contractor performing the work to review quantities and finalize pricing and materials based on current prices.

Estimating Services

Date: 07/27/2018

Scope	Qty	Unit	Est. Labor Costs	Est. Equipment (Tax Incl.)	Est. Mat. (Tax Incl.)	Est. Sub Markup	Totals	Notes
Supervision	26.00	Wks	\$52,000.00				\$52,000.00	
Dumpsters	0.00	EA					\$0.00	
Equipment	1.00	LS					\$10,000.00	
Administrative								
Insurance								
Bond								
2 Sitework								
2.C Heavy Duty Concrete Pavement 6" Concrete over 6" Cab Over CSG	431.92	SF	\$1,285.39	\$0.00	\$1,456.55	0%	\$2,741.95	
Compacted Aggregate Base 5"	431.92	SF	\$82.93	\$57.32	\$345.87	0%	\$486.12	
Rebar #5 **	864.00	LF	\$601.34	\$0.00	\$613.91	0%	\$1,215.26	
2.C Concrete Sidewalk	5,786.57	SF	\$16,665.32	\$0.00	\$14,814.89	0%	\$31,480.21	
Concrete Curbs	744.00	LF	\$8,454.82	\$2,303.92	\$6,864.00	0%	\$17,622.74	
3 Concrete								
Concrete Walls								
3.Concrete Wall 12" Main	601.91	LF						
Concrete 12"	8,426.74	SF	\$83,930.33	\$5,778.12	\$68,429.51	0%	\$158,137.96	
#5 Rebar @12" O.C. Vert	10,954.76	LF	\$7,624.51	\$0.00	\$7,783.86	0%	\$15,408.37	
#4 Rebar @16" O.C. Horiz.	8,216.07	LF	\$4,436.68	\$0.00	\$4,262.59	0%	\$8,699.27	
3.Concrete Wall 8" Transition	25.03	LF						
Concrete 8"	350.42	SF	\$3,031.83	\$158.89	\$2,146.05	0%	\$5,336.78	
#5 Rebar @12" O.C. Vert	455.55	LF	\$317.06	\$0.00	\$323.69	0%	\$640.75	
#4 Rebar @16" O.C. Horiz.	341.66	LF	\$184.50	\$0.00	\$177.26	0%	\$361.75	
3.Concrete Wall 12" #7 Vert @6" O.C. & #5 @12" O.C. Horiz.	14.23	LF						
Concrete 12"	199.22	SF	\$1,984.23	\$136.60	\$1,617.77	0%	\$3,738.60	
#7 Rebar @6" O.C. Vert	517.97	LF	\$640.21	\$0.00	\$847.08	0%	\$1,487.30	
#5 Rebar @12" O.C. Horiz	258.99	LF	\$180.25	\$0.00	\$184.02	0%	\$364.28	
3.Concrete Wall 12" #7 Vert @12" O.C. & #5 @12" O.C. Horiz.	89.87	LF						
Concrete 12"	1,258.18	SF	\$12,531.47	\$862.72	\$10,217.08	0%	\$23,611.27	
#7 Rebar @12" O.C. Vert	1,635.63	LF	\$2,021.64	\$0.00	\$2,674.89	0%	\$4,696.53	
#5 Rebar @12" O.C. Horiz	1,635.63	LF	\$1,138.40	\$0.00	\$1,162.19	0%	\$2,300.59	
3.Concrete Rail 12" #7 Vert @6" O.C. & #5 Horiz @12" O.C.	100.53	LF						
Concrete 12"	351.86	SF	\$3,504.48	\$241.26	\$2,857.25	0%	\$6,602.98	
#7 Rebar @6" O.C. Vert	914.82	LF	\$1,130.72	\$0.00	\$1,496.09	0%	\$2,626.81	
#5 Rebar @12" O.C. Horiz	457.41	LF	\$318.36	\$0.00	\$325.01	0%	\$643.37	

Concrete Slabs								
3.Slab Basement 32" #7 @18" O.C. EW BOTT & #7 @9" O.C. EW TOP	24,613.23	SF						
Concrete 32" ***	24,613.23	SF	\$366,244.86	\$0.00	\$448,213.47	0%	\$814,458.33	
#7 Rebar @18" O.C. EW Bottom	42,662.93	LF	\$52,731.38	\$0.00	\$69,770.21	0%	\$122,501.60	
#7 Rebar @9" O.C. EW Top	85,325.86	LF	\$105,462.77	\$0.00	\$139,540.42	0%	\$245,003.19	
3.Concrete Slab 12" #5 @12" O.C. EW B & #5 @8" O.C. EW T	1,065.09	SF						
Concrete 12"	1,065.09	SF	\$4,256.10	\$376.94	\$7,531.91	0%	\$12,164.95	
#5 Rebar @12" O.C. EW Bottom	2,769.23	LF	\$1,927.39	\$0.00	\$1,967.67	0%	\$3,895.05	
#5 Rebar @8" O.C. EW Top	10,800.01	LF	\$7,516.81	\$0.00	\$7,673.90	0%	\$15,190.71	
3.Concrete Slab 12" with 3TB	8,304.79	SF						
Concrete 12"	8,304.79	SF	\$33,185.94	\$2,939.10	\$58,728.31	0%	\$94,853.35	
#5 Rebar @12" O.C. Top & Bottom	21,592.45	LF	\$15,028.35	\$0.00	\$15,342.42	0%	\$30,370.77	
2TB & 12" Slab	123.63	SF						
Concrete 12"	123.63	SF	\$494.03	\$43.75	\$874.26	0%	\$1,412.04	
#5 Rebar @12" O.C. Top & Bottom	321.44	LF	\$223.72	\$0.00	\$228.40	0%	\$452.12	
3.Concrete Slab 10" with 1B	12,901.36	SF						
Concrete 10"	12,901.36	SF	\$51,553.83	\$4,565.84	\$78,865.33	0%	\$134,985.01	
#4 Rebar @24" O.C. EW	16,771.77	LF	\$9,056.75	\$0.00	\$8,701.38	0%	\$17,758.13	
3.Concrete Slab 10" with 4B	384.85	SF						
Concrete 10"	384.85	SF	\$1,537.86	\$136.20	\$2,352.57	0%	\$4,026.63	
#5 Rebar @18" O.C. EW	667.07	LF	\$464.28	\$0.00	\$473.99	0%	\$938.27	
3.Concrete Slab 10" with 3TB	2,670.17	SF						
Concrete 10"	2,670.17	SF	\$10,670.00	\$944.98	\$16,322.61	0%	\$27,937.59	
#5 Rebar @12" O.C. Top & Bottom	6,942.44	LF	\$4,831.94	\$0.00	\$4,932.92	0%	\$9,764.86	
3.Concrete Slab 8" with 2TB	3,765.73	SF						
Concrete 8"	3,765.73	SF	\$14,324.84	\$1,291.06	\$19,409.61	0%	\$35,025.50	
#5 Rebar @12" O.C. Top & Bottom	9,790.90	LF	\$6,814.47	\$0.00	\$6,956.88	0%	\$13,771.34	
3.Concrete Slab 8" with 1B	14,715.29	SF						
Concrete 8"	14,715.29	SF	\$55,976.96	\$5,045.06	\$75,846.64	0%	\$136,868.66	
#4 Rebar @24" O.C. EW	19,129.88	LF	\$10,330.13	\$0.00	\$9,924.79	0%	\$20,254.92	
3.Concrete Slab 8" with 4B	97.67	SF						
Concrete 8"	97.67	SF	\$371.54	\$33.49	\$503.42	0%	\$908.44	
#5 Rebar @18" O.C. EW	169.29	LF	\$117.83	\$0.00	\$120.29	0%	\$238.12	
3.Concrete Slab 13" with 2TB	129.97	SF						
Concrete 13"	129.97	SF	\$623.23	\$46.00	\$1,102.92	0%	\$1,772.15	
#5 Rebar @12" O.C. Top & Bottom	337.92	LF	\$235.19	\$0.00	\$240.11	0%	\$475.30	
3.Concrete Slab 13" with 1B	14,732.52	SF						
Concrete 13"	14,732.52	SF	\$70,645.38	\$5,213.90	\$125,019.33	0%	\$200,878.61	
#4 Rebar @24" O.C. EW	19,152.28	LF	\$10,342.23	\$0.00	\$9,936.41	0%	\$20,278.64	
Post Tension for All Slabs ***	83,504.30	SF					\$417,521.50	
Additional Rebar for Slabs								
F1B	41.00	EA						
#7 Rebar L=16'	656.00	LF	\$810.82	\$0.00	\$1,072.81	0%	\$1,883.63	
F2B	3.00	EA						
#7 Rebar L=12'	36.00	LF	\$44.50	\$0.00	\$58.87	0%	\$103.37	

F3B		12.00	EA						
#7 Rebar L=16'		192.00	LF	\$237.31	\$0.00	\$313.99	0%	\$551.31	
F4B		11.00	EA						
#7 Rebar (8) L=14'		1,232.00	LF	\$1,522.75	\$0.00	\$2,014.79	0%	\$3,537.54	
F5B		15.00	EA						
#7 Rebar (6) L=15'		1,350.00	LF	\$1,668.60	\$0.00	\$2,207.77	0%	\$3,876.37	
F7B		4.00	EA						
#7 Rebar (12) L=21'		1,008.00	LF	\$1,245.89	\$0.00	\$1,648.47	0%	\$2,894.35	
F8B		7.00	EA						
#7 Rebar (12) L=18'		1,512.00	LF	\$1,868.83	\$0.00	\$2,472.70	0%	\$4,341.53	
F6B		5.00	EA						
#7 Rebar (6) L=12'		360.00	LF	\$444.96	\$0.00	\$588.74	0%	\$1,033.70	
F11B		2.00	EA						
#7 Rebar (10) L=8'		160.00	LF	\$197.76	\$0.00	\$261.66	0%	\$459.42	
F12B		2.00	EA						
#7 Rebar (8) L=16'		256.00	LF	\$316.42	\$0.00	\$418.66	0%	\$735.07	
F13B		1.00	EA						
#7 Rebar (15) L=16'		240.00	LF	\$296.64	\$0.00	\$392.49	0%	\$689.13	
F30B		1.00	EA						
#7 Rebar L=18'		18.00	LF	\$22.25	\$0.00	\$29.44	0%	\$51.68	
F9B		9.00	EA						
#7 Rebar (8) L=18'		1,296.00	LF	\$1,601.86	\$0.00	\$2,119.46	0%	\$3,721.31	
F10B		2.00	EA						
#7 Rebar L=6'		12.00	LF	\$14.83	\$0.00	\$19.62	0%	\$34.46	
F15B		1.00	EA						
#7 Rebar (10) L=25'		250.00	LF	\$309.00	\$0.00	\$408.85	0%	\$717.85	
F16B		2.00	EA						
#7 Rebar L=8'-6"		17.00	LF	\$21.01	\$0.00	\$27.80	0%	\$48.81	
F17B		2.00	EA						
#7 Rebar (6) L=6'		72.00	LF	\$88.99	\$0.00	\$117.75	0%	\$206.74	
F14B		2.00	EA						
#7 Rebar (6) L=8'		96.00	LF	\$118.66	\$0.00	\$157.00	0%	\$275.65	
F18B		1.00	EA						
#7 Rebar (10) L=6'		60.00	LF	\$74.16	\$0.00	\$98.12	0%	\$172.28	
F20B		1.00	EA						
#7 Rebar (15) L=18'		270.00	LF	\$333.72	\$0.00	\$441.55	0%	\$775.27	
F21B		2.00	EA						
#7 Rebar L=30'		60.00	LF	\$74.16	\$0.00	\$98.12	0%	\$172.28	
F22B		7.00	EA						
#7 Rebar L=12'		84.00	LF	\$103.82	\$0.00	\$137.37	0%	\$241.20	
F23B		1.00	EA						
#7 Rebar (9) L=14'		126.00	LF	\$155.74	\$0.00	\$206.06	0%	\$361.79	

F27B	1.00	EA						
#7 Rebar (3) L=6'	18.00	LF	\$22.25	\$0.00	\$29.44	0%	\$51.68	
F28B	1.00	EA						
#7 Rebar (14) L=13'-6"	189.00	LF	\$233.60	\$0.00	\$309.09	0%	\$542.69	
F25B	2.00	EA						
#7 Rebar (8) L=8'	128.00	LF	\$158.21	\$0.00	\$209.33	0%	\$367.54	
F29B	1.00	EA						
#7 Rebar (3) L=8'	24.00	LF	\$29.66	\$0.00	\$39.25	0%	\$68.91	
F26B	3.00	EA						
#7 Rebar (8) L=12'	288.00	LF	\$355.97	\$0.00	\$470.99	0%	\$826.96	
1T	28.00	EA						
#5 Rebar (10) L=12'	3,360.00	LF	\$2,338.56	\$0.00	\$2,387.43	0%	\$4,725.99	
3T	32.00	EA						
#5 Rebar (12) L=14'	5,376.00	LF	\$3,741.70	\$0.00	\$3,819.89	0%	\$7,561.59	
12T	20.00	EA						
#5 Rebar (8) L=14'	2,240.00	LF	\$1,559.04	\$0.00	\$1,591.62	0%	\$3,150.66	
24T	1.00	EA						
#5 Rebar (10) L=20'	200.00	LF	\$139.20	\$0.00	\$142.11	0%	\$281.31	
2T	14.00	EA						
#5 Rebar (14) L=14'	2,744.00	LF	\$1,909.82	\$0.00	\$1,949.74	0%	\$3,859.56	
15T	3.00	EA						
#5 Rebar (8) L=14'	336.00	LF	\$233.86	\$0.00	\$238.74	0%	\$472.60	
14T	3.00	EA						
#5 Rebar (14) L=10'	420.00	LF	\$292.32	\$0.00	\$298.43	0%	\$590.75	
18T	5.00	EA						
#5 Rebar (18) L=13'	1,170.00	LF	\$814.32	\$0.00	\$831.34	0%	\$1,645.66	
20T	8.00	EA						
#5 Rebar (24) L=14'	2,688.00	LF	\$1,870.85	\$0.00	\$1,909.95	0%	\$3,780.79	
23T	2.00	EA						
#5 Rebar (20) L=12'	480.00	LF	\$334.08	\$0.00	\$341.06	0%	\$675.14	
11T	41.00	EA						
#5 Rebar (8) L=12'	3,936.00	LF	\$2,739.46	\$0.00	\$2,796.71	0%	\$5,536.16	
25T & 4TB	1,925.07	LF						
#5 Rebar L=6' @12" O.C.	15,015.55	LF	\$10,450.82	\$0.00	\$10,669.23	0%	\$21,120.05	
#5 Rebar (2)	3,850.14	LF	\$2,679.70	\$0.00	\$2,735.70	0%	\$5,415.40	
25T (only)	416.02	LF						
#5 Rebar L=6' @12" O.C.	3,244.96	LF	\$2,258.49	\$0.00	\$2,305.69	0%	\$4,564.18	
22T	3.00	EA						
#5 Rebar (8) L=30'	720.00	LF	\$501.12	\$0.00	\$511.59	0%	\$1,012.71	
5T	24.00	EA						
#5 Rebar (8) L=6'	1,152.00	LF	\$801.79	\$0.00	\$818.55	0%	\$1,620.34	
9T	7.00	EA						

	#5 Rebar (10) L=10'	700.00	LF	\$487.20	\$0.00	\$497.38	0%	\$984.58
	1TB	111.14	LF					
	#5 Rebar L=6' @6" O.C.	3,467.57	LF	\$2,413.43	\$0.00	\$2,463.86	0%	\$4,877.29
	3TB	253.96	SF					
	#5 Rebar L=12' @12" O.C.	660.30	LF	\$459.57	\$0.00	\$469.17	0%	\$928.74
	8T	10.00	EA					
	#5 Rebar (8) L=10'	800.00	LF	\$556.80	\$0.00	\$568.44	0%	\$1,125.24
	28T	1.00	EA					
	#8 Rebar (5) L=8'	40.00	LF	\$64.80	\$0.00	\$74.44	0%	\$139.24
	26T	1.00	EA					
	#5 Rebar L=14'	14.00	LF	\$9.74	\$0.00	\$9.95	0%	\$19.69
	27T	1.00	EA					
	#8 Rebar (12) L=11'	132.00	LF	\$213.84	\$0.00	\$245.65	0%	\$459.49
	3B	1.00	EA					
	#8 Rebar (9) L=30'	270.00	LF	\$437.40	\$0.00	\$502.46	0%	\$939.86
	3.Beam 18"x17" w/5TB	32.34	LF					
	#8 Rebar (4)	129.36	LF	\$209.56	\$0.00	\$240.73	0%	\$450.30
	21T	1.00	EA					
	#5 Rebar (20) L=20'	400.00	LF	\$278.40	\$0.00	\$284.22	0%	\$562.62
	7T	2.00	EA					
	#5 Rebar (12) L=6'	144.00	LF	\$100.22	\$0.00	\$102.32	0%	\$202.54
	19T	3.00	EA					
	#5 Rebar (20) L=18'	1,080.00	LF	\$751.68	\$0.00	\$767.39	0%	\$1,519.07
	30T	10.00	EA					
	#5 Rebar (4) L=14'	560.00	LF	\$389.76	\$0.00	\$397.91	0%	\$787.67
	6T	10.00	EA					
	#5 Rebar (10) L=6'	600.00	LF	\$417.60	\$0.00	\$426.33	0%	\$843.93
	17T	2.00	EA					
	#5 Rebar (8) L=28'	448.00	LF	\$311.81	\$0.00	\$318.32	0%	\$630.13
	2TB	70.38	LF					
	#5 Rebar L=6' @12" O.C.	1,097.93	LF	\$764.16	\$0.00	\$780.13	0%	\$1,544.29
	4T	2.00	EA					
	#5 Rebar (14) L=18'	504.00	LF	\$350.78	\$0.00	\$358.11	0%	\$708.90
	16T	1.00	EA					
	#5 Rebar (10) L=20'	200.00	LF	\$139.20	\$0.00	\$142.11	0%	\$281.31
	3TB	112.64	LF					
	#5 Rebar L=12' @12" O.C.	3,514.37	LF	\$2,446.00	\$0.00	\$2,497.12	0%	\$4,943.12
	2B	150.14	LF					
	#4 Rebar L=18' @18" O.C.	2,342.18	LF	\$1,264.78	\$0.00	\$1,215.15	0%	\$2,479.93
	10T	1.00	EA					
	#5 Rebar (14) L=10'	140.00	LF	\$97.44	\$0.00	\$99.48	0%	\$196.92
	13T	2.00	EA					

#5 Rebar (10) L=10'	200.00	LF	\$139.20	\$0.00	\$142.11	0%	\$281.31
6TB	14.54	LF					
#5 Rebar L=12' @9" O.C.	604.86	LF	\$420.99	\$0.00	\$429.78	0%	\$850.77
Concrete Shear Walls							
3.Shear Wall 14"	6,041.75	SF					
Concrete 14"	6,041.75	SF	\$72,211.00	\$4,142.76	\$58,874.58	0%	\$135,228.34
3.Shear Wall 12"	1,784.64	SF					
Concrete 12"	1,784.64	SF	\$17,775.01	\$1,223.71	\$14,492.20	0%	\$33,490.93
Rebar for Shear Walls							
3.SW 20 Rebar #5 @12" O.C. Horiz & #5 @12" O.C. Vert	1,023.80	SF					
#5 Rebar @12" O.C. Horiz. & Vert. Both Sides	5,323.76	LF	\$3,705.34	\$0.00	\$3,782.77	0%	\$7,488.11
3.SW 15 Rebar #5 @12" O.C. Horiz & #6 @12" O.C. Vert	371.65	SF					
#5 Rebar @12" O.C. Horiz Both Sides	966.29	LF	\$672.54	\$0.00	\$686.59	0%	\$1,359.13
#6 Rebar @12" O.C. Vert Both Sides	966.29	LF	\$892.85	\$0.00	\$969.95	0%	\$1,862.80
3.SW 15 Rebar #7 Vertical (12) & #4 Ties @4" O.C.	74.85	LF					
#7 Rebar (12) Vertical	898.20	LF	\$1,110.18	\$0.00	\$1,468.90	0%	\$2,579.08
#4 Ties @4" O.C.	224.55	EA	\$242.51	\$0.00	\$1,517.02	0%	\$1,759.53
3.SW 14 Rebar #5 @12" O.C. Vert & #5 @8" O.C. Horiz.	646.59	SF					
#5 Rebar @12" O.C. Vert Both Sides	1,681.13	LF	\$1,170.07	\$0.00	\$1,194.52	0%	\$2,364.59
#5 Rebar @8" O.C. Horiz. Both Sides	2,521.70	LF	\$1,755.10	\$0.00	\$1,791.78	0%	\$3,546.89
3.SW 10 Rebar #5 @12" O.C. Horiz	673.28	SF					
#5 Rebar @12" O.C. Horiz. Both sides	1,750.53	LF	\$1,218.37	\$0.00	\$1,243.83	0%	\$2,462.20
3.SW 10 Rebar #7 Vert (6) & #4 Ties @4" O.C.	138.32	LF					
#7 Rebar (6) Vertical	829.92	LF	\$1,025.78	\$0.00	\$1,357.24	0%	\$2,383.02
#4 Ties @4" O.C.	414.96	EA	\$448.16	\$0.00	\$2,803.40	0%	\$3,251.55
3.SW 10 Rebar #7 Vert (10) & #4 Ties @4" O.C.	34.44	LF					
#7 Rebar (10) Vertical	344.40	LF	\$425.68	\$0.00	\$563.23	0%	\$988.90
#4 Ties @4" O.C.	103.32	EA	\$111.59	\$0.00	\$698.01	0%	\$809.60
3.SW 9 Rebar #5 @12" O.C. Horiz & #5 @12" O.C. Vert	752.83	SF					
#5 Rebar @12" O.C. Horiz. & Vert. Both Sides	3,914.72	LF	\$2,724.64	\$0.00	\$2,781.58	0%	\$5,506.23
3.SW 9 Rebar #7 Vert (6) & #4 Ties @4" O.C.	53.93	LF					
#7 Rebar (6) Vertical	323.58	LF	\$399.94	\$0.00	\$529.18	0%	\$929.12
#4 Ties @4" O.C.	161.79	EA	\$174.73	\$0.00	\$1,093.02	0%	\$1,267.76
3.SW 9 Rebar #7 Vert (12) & #4 Ties @4" O.C.	34.29	LF					
#7 Rebar (12) Vertical	411.48	LF	\$508.59	\$0.00	\$672.93	0%	\$1,181.52
#4 Ties @4" O.C.	102.87	EA	\$111.10	\$0.00	\$694.97	0%	\$806.07
3.SW 8 Rebar #5 @12" O.C. Horiz & #5 @12" O.C. Vert	708.13	SF					
#5 Rebar @12" O.C. Horiz. & Vert. Both Sides	3,682.28	LF	\$2,562.86	\$0.00	\$2,616.42	0%	\$5,179.29
3.SW 8 Rebar #7 Vert (6) & #4 Ties @4" O.C.	87.62	LF					
#7 Rebar (6) Vertical	525.72	LF	\$649.79	\$0.00	\$859.75	0%	\$1,509.54
#4 Ties @4" O.C.	262.86	EA	\$283.89	\$0.00	\$1,775.84	0%	\$2,059.72
3.SW 7 Rebar #5 @12" O.C. Horiz & #5 @12" O.C. Vert	359.24	SF					
#5 Rebar @12" O.C. Horiz. & Vert. Both Sides	1,868.05	LF	\$1,300.16	\$0.00	\$1,327.33	0%	\$2,627.49

3.SW 7 Rebar #7 Vert (6) & #4 Ties @4" O.C.	68.66	LF						
#7 Rebar (6) Vertical	411.96	LF	\$509.18	\$0.00	\$673.71	0%	\$1,182.89	
#4 Ties @4" O.C.	205.98	EA	\$222.46	\$0.00	\$1,391.56	0%	\$1,614.02	
3.SW 6 Rebar #5 @12" O.C. Horiz & #5 @12" O.C. Vert	708.11	SF						
#5 Rebar @12" O.C. Horiz. & Vert. Both Sides	3,682.17	LF	\$2,562.79	\$0.00	\$2,616.35	0%	\$5,179.14	
3.SW 6 Rebar #7 Vert (6) & #4 Ties @4" O.C.	124.28	LF						
#7 Rebar (6) Vertical	745.68	LF	\$921.66	\$0.00	\$1,219.47	0%	\$2,141.13	
#4 Ties @4" O.C.	372.84	EA	\$402.67	\$0.00	\$2,518.84	0%	\$2,921.51	
3.SW 5 Rebar #5 @12" O.C. Horiz & #5 @12" O.C. Vert	379.08	SF						
#5 Rebar @12" O.C. Horiz. & Vert. Both Sides	1,971.22	LF	\$1,371.97	\$0.00	\$1,400.64	0%	\$2,772.60	
3.SW 5 Rebar #7 Vert (6) & #4 Ties @4" O.C.	68.64	LF						
#7 Rebar (6) Vertical	411.84	LF	\$509.03	\$0.00	\$673.52	0%	\$1,182.55	
#4 Ties @4" O.C.	205.92	EA	\$222.39	\$0.00	\$1,391.16	0%	\$1,613.55	
3.SW 4 Rebar #5 @12" O.C. Vert & #5 @12" O.C. Horiz	494.01	SF						
#5 Rebar @12" O.C. Horiz. & Vert. Both Sides	2,568.85	LF	\$1,787.92	\$0.00	\$1,825.29	0%	\$3,613.21	
3.SW 4 Rebar #7 Vert (6) & #4 Ties @4" O.C.	111.56	LF						
#7 Rebar (6) Vertical	669.36	LF	\$827.33	\$0.00	\$1,094.66	0%	\$1,921.99	
#4 Ties @4" O.C.	334.68	EA	\$361.45	\$0.00	\$2,261.04	0%	\$2,622.49	
3.SW 3 Rebar #5 @12" O.C. Vert & #5 @12" O.C. Horiz	369.08	SF						
#5 Rebar @12" O.C. Horiz. & Vert. Both Sides	1,919.22	LF	\$1,335.77	\$0.00	\$1,363.69	0%	\$2,699.46	
3.SW 3 Rebar #7 Vert (6) & #4 Ties @4" O.C.	69.52	LF						
#7 Rebar (6) Vertical	417.12	LF	\$515.56	\$0.00	\$682.15	0%	\$1,197.71	
#4 Ties @4" O.C.	208.56	EA	\$225.24	\$0.00	\$1,408.99	0%	\$1,634.24	
3.SW 2 Rebar #5 @12" O.C. Horiz & #5 @12" O.C. Vert	679.20	SF						
#5 Rebar @12" O.C. Horiz. & Vert. Both Sides	3,531.84	LF	\$2,458.16	\$0.00	\$2,509.53	0%	\$4,967.69	
3.SW 2 Rebar #7 Vert (6) & #4 Ties @4" O.C.	118.24	LF						
#7 Rebar (6) Vertical	709.44	LF	\$876.87	\$0.00	\$1,160.21	0%	\$2,037.07	
#4 Ties @4" O.C.	354.72	EA	\$383.10	\$0.00	\$2,396.43	0%	\$2,779.52	
3.SW 1 Rebar #5 @12" O.C. Horiz & #5 @12" O.C. Vert	657.77	SF						
#5 Rebar @12" O.C. Horiz. & Vert. Both Sides	3,420.40	LF	\$2,380.60	\$0.00	\$2,430.35	0%	\$4,810.95	
3.SW 1 Rebar #7 Vert (6) & #4 Ties @4" O.C.	104.34	LF						
#7 Rebar (6) Vertical	626.04	LF	\$773.79	\$0.00	\$1,023.81	0%	\$1,797.60	
#4 Ties @4" O.C.	313.02	EA	\$338.06	\$0.00	\$2,114.71	0%	\$2,452.77	
Concrete Columns								
3.CC1	8.00	EA						
Concrete 14"x20"	634.67	SF	\$1,652.67	\$364.99	\$3,478.83	0%	\$5,496.50	
#8 Rebar (10)	1,456.00	LF	\$2,358.72	\$0.00	\$2,709.55	0%	\$5,068.27	
#4 Ties @4" O.C.	336.00	EA	\$362.88	\$0.00	\$2,269.96	0%	\$2,632.84	
3.CC3	6.00	EA						
Concrete 14"x20"	1,037.00	SF	\$2,700.35	\$596.37	\$5,684.16	0%	\$8,980.88	
#7 Rebar (10)	2,379.00	LF	\$2,940.44	\$0.00	\$3,890.57	0%	\$6,831.02	
#4 Ties @4" O.C.	549.00	EA	\$592.92	\$0.00	\$3,708.95	0%	\$4,301.87	
3.CC7	10.00	EA						
Concrete 14"x20"	2,312.57	SF	\$6,021.92	\$1,329.94	\$12,675.99	0%	\$20,027.86	
#8 Rebar (10)	5,305.30	LF	\$8,594.59	\$0.00	\$9,872.91	0%	\$18,467.50	
#4 Ties @4" O.C.	1,224.30	EA	\$1,322.24	\$0.00	\$8,271.15	0%	\$9,593.40	

